Abstract Notification dated 4th February 1936.

The attention of the public is invited to the Notification, calling for tenders for extending the Workshop attached to the College of Engineering, Bangalore, on pages 171-172 of Part VI of the *Mysore Gazette*, dated 6th February 1936.

The last date for receiving tenders is 15th February 1936.

N. KRISHNA IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 3rd February 1936.

The attention of the public is hereby invited to the detailed Notification, inviting sealed tenders for constructing a Travellers' Bungalow at Channapatna, Channapatna Taluk, published on pages 173-174 of Part VI of the *Mysore Gazette*, dated 6th February 1936.

The last date of tender is 2 P.M. on 15th February 1936 and the earnest money to accompany the tender is Rs. 250.

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 23rd—25th January 1936.

The attention of the public is invited to the notification published on page 133 of the *Mysore Gazette*, dated 30th January 1936, inviting tenders for the remaining maintenance work of Manchenahalli Tank, Register No. 69 of Goribidnur Taluk.

The last date for the receipt of tenders in this office is up to 2 P.M. on 15th February 1936.

Notification dated 1st February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 28th February 1936, for the restoration of Gollapalli Ayyavarakere, Register No. 518, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Gollapalli Ayyavarakere, Register No. 518, Bagepalli Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for Restoring Gollapalli Ayyavarakere, Register No. 518, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
	I BUND AT R.L. 55.50, TOP WIDTH 4½', SLOPES FRONT 1½ TO 1 AND 2 TO 1, REAR SLOPE 2 TO 1.				
1	I Clearing Jungle and removing ant-hills and filling them with sand	Grade	3 0 0	16	
2	Cutting grips and trenches to Bund for the receipt of new earth	,,	3 0 0	16	
3	Earthwork to Bund with watering and consolidation	C.yd.	0 3 0	6,339	
	(a) Closing the leaks 1 to 5 Grades and filling with a mixture of clay and gravel ..	,,	0 6 0	440	
4	Turfing the slopes	S.yd.	0 0 9	5,469	
5	Removing and resetting of old stone revetment with jelly	C.yd.	0 8 0	200	
6	New stone work with jelly backing ..	,,	1 8 0	211	
7	Providing and fixing new grade stones including figuring and painting, etc., complete	Each	1 12 0	16	
8	Do Index stones do ..	,,	0 6 0	16	
9	Do B.M. stones do ..	,,	2 8 0	2	
10	Do Register No. and date stones	,,	3 0 0	1	
11	Do Gauge stone	,,	15 0 0	1	
	II. SLUICE AT R. L. 42·00.				
1	Providing plug and rod with locking arrangements	Each	30 0 0	1	
	III. RAISING THE RIGHT WASTE WEIR, 32 FT. LONG BY ½ FT. FROM R.L. 50·00 TO 50·50. LENGTH AFTER RAISING WOULD BE 34 FT.				
1	Removing and refixing burnt stone slabs ..	S.ft.	0 1 6	57	
2	Burnt Brick in surki mortar	C.ft.	0 4 6	40	
3	Surki concrete coping	C.ft.	0 4 3	8	
4	Plastering with surki mortar	Sqr.	3 12 0	0·46	
5	Joggle joints	No.	0 12 0	4	
	IV. RAISING THE LEFT WASTE WEIR 111 FT LONG FROM R. L. 50.00 TO R. L. 50·50.				
1	Removing and refixing burnt stone slabs ..	S.ft.	0 1 6	171	
2	Burnt Brick in surki mortar	C.ft.	0 4 6	98	
3	Surki concrete coping	C.ft.	0 4 3	28	
4	Plastering with surki mortar	Sqr.	3 12 0	1·17	
5	Joggle joints	No.	0 12 0	15	

Notification, dated 5th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 2nd March 1936, for "Closing the breach and extending left waste weir of Thimmapalli Nayankere, Register No. 859, Bagepalli Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Superintending Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4 Each tender must be accompanied by a deposit of Rs. 750 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for closing the breach and extending left waste weir of Thimmapalli Nayankere, Register No. 859, Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 1,000 has to be shown every month.

Abstract estimate for closing the breaches and extending the waste weir of Thimmapalli Nayankere, Register No. 859, Bagepalli Taluk.

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I. FILLING IN THE BREACHES.				
1	Clearing site and removing boulders and bailing water at breach site	Lumpsum	..	..	100
2	Removing silt and slush at breached site	C.yd.	0 3 0	3,068	575
3	Excavating foundation trenches and grips for the seat of new earth and using the earth to rear side of bund	,,	0 3 0	1,160	218
4	Clay puddle for core wall	,,	0 12 0	1,025	769
5	Providing jelly drain	,,	1 0 0	104	104
6	Earthwork to bund with watering and consolidation including lead and lift, etc., complete with 50 per cent clay and gravel (gravel to be carted from half mile)	,,	0 8 0	14,250	7,125
	(a) Extra rate for consolidating earth got from foundations of bund including watering and consolidation	,,	0 2 6	1,160	181
7	Gravel backing to revetment, $\frac{3}{4}$ ft. in thickness	,,	0 10 0	289	180
8	New stone revetment	,,	1 8 0	910	1,365
9	Removing and resetting old stone revetment with new jelly here and there	Lumpsum	..	..	20
10	Turfing the slopes	,,	0 0 9	2,467	463
	Total	..	..	..	11,100

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	II. REPAIRS TO THE EXISTING WASTE WEIR 109 FT. AT R.L. 50·00 AND EXTENDING IT ON THE EITHER SIDES. THE TOTAL LENGTH WILL BE 35+109+(10 return) +46=200 FT. AT R.L. 50·00.				
	(A) Extending the Weir 35 ft. to the left.				
1	Earthwork excavating foundation and filling in	C.yd.	0 3 0	48	9
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 3	115	31
3	Burnt size stone in surki mortar	,,	0 5 0	171	54
4	Burnt stone slabs 6″ thick, dressed and fixed	S.ft.	0 5 0	141	44
5	Pointing with cement mortar	Sqr.	4 0 0	2·1	9
6	Providing joggle joints	Each	0 12 0	5	4
7	Rough stone work for apron	C.yd.	1 8 0	44	66
	Total ..	..	..	..	217
	(B) Repairs to the existing Waste Weir 109 ft. at R.L. 50·00.				
1	Excavating in disintegrated soft rock and dismantling right return, etc.	Lumpsum	..	..	20
2	Size stone in surki mortar	C.ft.	0 5 0	135	36
3	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 5 0	228	71
4	Plastering with surki mortar	Sqr.	4 0 0	8·25	33
5	Rough stone work for apron	C.yd.	1 8 0	158	237
6	Providing and fixing cast iron pipes for sluice 6″ in diameter, including Railway freight, cart hire, etc., complete ..	R.ft.	3 0 0	24	72
7	Repairs to sluice No. 3	Lumpsum	..	..	25
	Total ..	..	..	..	494
	(C) Deviating the Bund and extending the Weir by 46 ft. on the right.				
1	Cutting old bund and using the earth for the deviation of bund	C.yd.	0 3 0	1,300	244
2	Removing existing revetment in the old bund and using the same for the deviated portion and resetting the same with new jelly	,,	0 8 0	107	54
3	Excavating grips and trenches for the seat of new bund and using the earth for rear slope watering and consolidating including extra rate for the same ..	,,	0 5 0	552	166
4	Earthwork to bund watering and consolidating including lead and lift	,,	0 4 0	173	43
	(*a*) Extra rate for consolidating earth got from old bund and draft and approaches of Waste Weir	,,	0 2 0	1,411	176
5	Excavation for masonry corewall in disintigrated soft chattu soil	,,	0 4 0	20	5
6	Benching rock, half feet depth	S.ft.	0 8 0	180	90
7	Burnt size stone in surki mortar	C.ft.	0 5 0	450	141
8	New stone revetment	C.yd.	1 8 0	132	198
9	Turfing the slopes	S.yd.	0 0 9	700	33

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Weir extension at right side by 46 ft.				
10	Excavating in hard gravelly soil mixed with boulders and using the earth for the training bank	C.yd.	0 4 0	463	116
11	Blasting rock at the approach site and using the same for revetment	,,	2 8 0	39	97
12	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	187	47
13	Burnt size stone in surki mortar	,,	0 5 0	364	114
14	Painting with cement mortar	Sqr.	4 0 0	9.34	38
15	Burnt stone slabs 6" thick dressed and fixed	S.ft.	0 5 0	239	75
16	Joggle joints, 8 ft. c to c	Each	0 12 0	6	5
17	New stone work for apron	C.yd.	1 8 0	45	68
	Total ..	..	..	..	2,421

GENERAL ABSTRACT.

		Rs.
I.	Filling the Breaches	11,100
II.	Waste Weir	2,421
III.	Miscellaneous	450
	Total ..	13,971
	Contingencies at 5 per cent	699
	Temporary Establishment 5 per cent	700
	Grand Total ..	15,370

N. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 23rd January 1936.

The attention of the public is invited to the detailed notification, calling for tenders for restoring Halehalli Hirikere Tank, Maddur Taluk, published on pages 134-135, Part VI of the *Mysore Gazette.*

The last date of receipt of tender is up to 2 P.M. on Monday the 17th February 1936.

Abstract Notification, dated 3rd February 1936.

The attention of the public is invited to the detailed notification, calling for tenders for constructing two additional rooms in the main building of the Middle School at Srirangapatam, on pages 175-176, Part VI of the *Mysore Gazette* dated 6th February 1936.

The last date of receipt of tender is up to 2 P.M. on 24th February 1936.

Abstract Notification, dated 3rd February 1936.

The attention of the public is invited to the detailed notification, calling for tenders for constructing Line Men's quarters at Honganahalli 48th mile on Kankanhalli-Malavalli Road, on pages 176-177, Part VI of the *Mysore Gazette* dated 6th February 1936.

The last date of the receipt of tender is up to 2 P.M. on 24th February 1936.

V. V. PATANKAR,
Executive Engineer.